

# Bronx Domestic Hot Water System Gets Electrified

*Innovative heat pump water heater from Laars uses CO2 refrigerant.*

**N**EW YORK, NY — 850 Bryant Ave is a 48-unit, six-story apartment complex in the Bronx. The property was selected for an electrification upgrade to improve energy efficiency, reduce carbon emissions, and modernize aging mechanical systems. As part of a broader initiative to enhance sustainability, the project focused on replacing its existing gas-fired domestic hot water (DHW) system with a high-performance commercial heat pump water heater.

Once the engineering team evaluated the site, however, they decided on an optimized hybrid approach in which the onboard control system automatically alternates between the heat pump and the existing gas-fired system based on real-time efficiency. This strategy aims to ensure optimal performance year-round while maximizing carbon footprint reduction and to provide redundancy by using existing equipment.

## Project Origins

The Association for Energy Affordability (AEA), a non-profit that specializes in energy efficiency and electrification upgrades for low and moderate-income buildings, often partners with local organizations to identify and implement high-efficiency solutions. AEA plays a key role in helping building owners access state and federal funding opportunities to support weatherization and electrification initiatives.

At 850 Bryant Ave, AEA collaborated with the South East Bronx Community Organization (SEBCO) and the Father Gigante organization to secure a grant through New York State's Weatherization Assistance Program (WAP). With funding in place, the team moved forward with a long-overdue upgrade to the building's aging mechanical systems, aiming to implement a domestic hot water solution that offered both high efficiency and low emissions—this aligns with New York City's carbon reduction goals and Local Law 97 compliance.

The installing contractor, A&C Plumbing, has been serving the community since 1982. The company boasts more than 50 years' worth of institutional knowledge, and holds both Oil Burner Equipment Installer, Class "B" and New York City Master Plumber Licenses. A&C specializes in gas conversions, #2, 4 & 6 oil burners, and combination dual fuel equipment using both scotch marine steel and cast-iron boilers. The company performs a wide range of hydronic repair, maintenance and installation services.

## The Right Equipment for the Job

After evaluating several options, the project team selected the Laars E-Therm® electric air-source heat pump water heater. One of the deciding factors was its use of



The Laars E-Therm Heat Pump Water Heater installed at 850 Bryant Avenue.



(Left to right) Kevin Gauthier of Laars Heating Systems and Greg Rathe of Rathe Associates standing in front of Laars Stratified Storage Tanks.

## Project Details

**Location:** Bronx, NY

**Building Specs:** 48-unit, six-story multifamily residence

**Scope:** Electrification of the domestic hot water system

**Key Stakeholders:** Association for Energy Affordability (AEA), Rathe Associates, A&C Plumbing, South East Bronx Community Organization (SEBCO), Father Gigante Organization

## Conclusion

The successful deployment of the Laars E-Therm and stratification tank system at 850 Bryant Ave highlights its potential as a scalable, efficient, and sustainable domestic hot water solution for multifamily buildings. By leveraging advanced heat pump technology and a natural refrigerant, this project sets a benchmark for future electrification upgrades in New York City's residential sector.

"The installation of the Laars E-Therm is going to make a huge difference in the performance of this building. We'll achieve greater efficiency with less equipment," said **Francis Rodriguez**, Weatherization Director at Association for Energy Affordability, Inc. "The plug-and-play design made our lives much easier and will continue to do so for those performing maintenance. We're so happy with how this project went. We'll most likely use this install as a prototype for all heat pump water heater installations going forward." **C**